

CRANE 17-18-19 GENERAL Outreach Backreach Total reach Above rail Below rail Total lift Under Sprd 2-20 Inder Crgo Beam ~5 min 171 lb/yd 13.2KV, 3 Phase 60Hz Speed (m/ /295.2 /295.2 65 LT 100 LT 72.0 m 26.0 m 128.5 m 54.5 m 180/590 16.0 m 70.5 m 80/590

- USCOE POM Dredging Phase 3 Final Survey Berth Depth of -50+2 referenced to MLLW, Tidal Epoch 1983-2001 as reported by NOAA.NOAA Tidal Station 872-3178.
- 2. ELEVATION (ELEV) ARE BASED ON HWL (MOST EXTREME CONDITION) AT GOVERNMENT CUT, MIAMI HARBOR ENTRANCE STATION. NO CORRECTION FOR SEA LEVELS ARE PERFORMED FOR VESSEL AT WHARF 3.
- 3. DIMENSIONS ARE IN MILLIMETERS; IN FEET AND INCHES WITHIN BRACKETS.

- 5. VESSEL DRAFT OF 14000 (45.9 FEET) ESTIMATED AT HWL. VESSEL ELEVATIONS ARE IN MILLIMETERS; IN FEET AND TENTHS WITHIN (PARENTHESES).
- If any discrepancy are noted and/or comments wish to be voiced, please contact Crane Management.
- . TARGET SHIP IS 23 WIDE WITH 11 HC ON DECK AND 12 SC BELOW DECK, 20,600 TEUs and 59m BEAM.

Changed Liftheight, below dock and Total Lift Height DESCRIPTION

Miami Dade County RFP No.: 00317 Dockside Container Handling STS Gantry Cranes, Port Miami Cranes No. 17-18-19

DOCKSIDE CONTAINER HANDLING STS GANTRY CRANES PORT MIAMI CRANES 17-18-19
PROJECT No.: 2015.029
GENERAL ARRANGEMENT
PORTMIAM





DATE: September 26, 2016

CAD DRAWING FILE: RFP00317 Model (4).dwg SCALE : TS | DRAWING NO.: POM-2